BANGALORE DIVISION.

Dated 18th September 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 25th September 1911, 5 P.M., for erecting iron record racks in two of the rooms of the General and Revenue Secretariat, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1911.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for erecting iron record racks in two of the rooms of the General and Revenue Secretariat, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract quantity of erecting record racks in Superintendents' room in the General and Revenue Secretariat at Bangalore :—

Iron Racks (21 *shelves*).

No.	*Items*	*Per*	*Quantity*
1.	Iron work cast iron shoes	E.	139
2.	L and T's fitting up cut lengths	Cwt.	223
3.	Boring holes including fitting bolts, etc.	E.	11,500
4.	Bolts and nuts of sizes do	dozen	479
5.	Iron curved brackets	E.	16
6.	Teakwood dental cross battens cut and fixed...	R.ft.	5,364
7.	Teakwood planking ¾" thick	Sqr.	9·11
8.	Do 1" platform	Do	16·30
9.	Do 1" above adjustable shelves	Do	44·34
10.	Glazed shutters, teak frames, etc., complete and fixing in L and T uprights with necessary woodwork	S.ft.	3,859
11.	Teakwood hand rails, complete	R.ft	302
12.	Do ladders with iron work railings, etc., complete	E.	2
13.	Painting zinc white (silicate)	Sqr.	123·00

Flooring, etc.

14.	Removing existing flooring and reflooring with Cuddapah slabs on 4" concrete bed including the cost of removal of concrete if it is laid fresh	Sqr.	11·56
15.	Dismantling cornice and replastering	R.ft.	189
16.	Do archways, etc.	E	2
17.	Whitewashing the room and sundry repairs	Lump sum	Rs.
18.	Removing existing galaries, etc....	R.ft.	158
19.	Sundry unforeseen works found necessary, during execution, such as closing up of doors and other entrances leading to adjoining rooms clearing records, etc.	Lump sum	Rs.

V. R. NIJAGAL,
Executive Engineer.